

BRUHAT BANGALORE MAHANAGARA PALIKE

MODIFIED SCHEDULE - B

Name of the work: Improvements to Drains of Vayunandhan Layout cross Roads in Kempapura in ward No-07, Byatarayanapura.

Sl. No.	Approved Qty.	Description	Unit	Rates	
				Sri. Prakash Naik H.	
				In Figures	In Words
1	266.85	Removing and Resetting of footpath Slabs(Page No 270 /S.no 37.56,PWD SR 2018-19)	Sqm	219.22	Rupees Two Hundred Nineteen and Twenty Two Paise Only
2	112.5	Removing and Resetting of Kerb stones(Page No 270 /S.no 37.57,PWD SR 2018-19)	Sqm	110.17	Rupees One Hundred Ten and Seventeen Paise Only
3	277.79	KSRRB 300-1,Earth work excavation by manual means in ordinary soil involving an average horizontal throw up to 2 meters and an average lift up to 1.5m,excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications (Item no19.1,Page no141, PWD SR 2018-19)	cum	145	Rupees One Hundred Forty Five Only
4	194.22	KSRB 2-1.1: Earthwork in surface excavation in ordinary soil for levelling and lowering the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe lines and cables) and removing the excavated stuff to a distance not exceeding 50m and lift upto 1.5m, excavated surface levelled and neatly dressed, disposed earth to be levelled after breaking of clods and neatly dressed as per specifications. (Page No 6 /S.no 2.1,PWD SR 2018-19)	cum	277.08	Rupees Two Hundred Seventy Seven and Eight Paise Only
5	501.60	Providing granite slabs of selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete do 7.5 cms thick(P.No 27 I.No 5.31.1)	Sqm	779	Rupees Seven Hundred Seventy Nine Only
6	1061.10	Providing granite slabs of selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete do 10 cms thick(P.No 27 I.No 5.31.2)	Sqm	1015	Rupees One Thousand Fifteen Only
7	26.97	KSRB 4.2.2 : Providing and laying in position plain cement concrete of mix M20 with OPC cement @ 320kgs, with 20mm and down size graded granite metal coarse aggregates @0.878cum and fine aggregates @0.459cum with superplastisre @ 3lts conforming to IS9103-1999Reffirmed 2008 machine mixed exceeding 15cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase, lintels, retaining walls, return walls, walls(any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc, including cost of all materials, labour HOM of machinery, curing, complete as per specifications. Specification. No. KBS 4.1,4.6, No. KBS 4.1,4.6, No. 14/ Item No. 4.11/ PWD SR 2018-19	cum	6297.27	Rupees Six Thousand Two Hundred Ninety Seven and Twenty Seven Paise Only
8	177.9	Providing and fixing 10cms thick pre cast RCC covering slab using reinforced cement concrete M20 mix with stone aggregate 20mm and down size including centering shuttering reinforcement and bar bending machine mixed concrete laid in layers not exceeding 15cm thick well compacted cost of all materials labour curing complete as per specifications(Data rate approved)	Sqm	2337	Rupees Two Thousand Three Hundred Thirty Seven Only


Signature of the contractor


Executive Engineer
21/09

Sl. No.	Qty.	Description	Unit	Rates	
				Sri. Prakash Naik H.	
				In Figures	In Words
9	28	Providing and fixing pre cast solid cement concrete kerb stones made out of C.C. 1:2:4 with top and bottom width 114 and 165 mm respectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting, including form work, curing, including cost of all materials, labour, hire charges of machinery, loading, unloading, lead and lift, transportation etc., complete.(pwd sr 2018-19 P.n o27 s.no 5.30)	No	454.02	Rupees Four Hundred Fifty Four and Two Paise Only
10	43.75	KSRB 800-1,Painting Two Coats after filling the surface with Synthetic enamel paint in approved Shades on new Plastered concrete surfaces,with materials,labour complete as per specifications,Morth chapter 8,(p.no.178,S.no.24,1 of PW ,P&IWD SR 2018-2019)	Sqm	89.02	Rupees Eighty Nine and Two Paise Only
11	12	KSRRB M2900-2.1.Laying Reinforced cement concrete pipe NP2/prestressed concrete pipe culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 but excluding excavation,protection works,backfilling,concrete and masanry works in head walls and parapets complete as per specifications.MORTH Specification No.2900 B.1200mm dia MORTH specification No.1000,2300 (Page No.255,Item No.34.7.8,pwd sr 2018-2019)	Sqm	6274	Rupees Six Thousand Two Hundred Seventy Four Only
12	1.34	Providing 100 mm and down size nominal size(Pg No.I.Item No.23)	cum	1037	Rupees One Thousand Thirty Seven Only
13	0.90	Providing 40mm and down size nominal size(Pg No.II.Item No.25)	cum	1146	Rupees One Thousand One Hundred Forty Six Only
14	0.90	Providing 20mm and down size nominal size(Pg No.II.Item No.28)	cum	1146	Rupees One Thousand One Hundred Forty Six Only
15	0.67	Providing fine aggregate 2.36mm nominal size(Pg No.II.Item No.32)	cum	1107	Rupees One Thousand One Hundred Seven Only
16	277.79	KSRB 100-1 Loading and unloading of stone aggregates / sand/ kanker/ Moorum /soil KSRRB M100-1 Placing tipper at loading with front end loader dumping turning for return trip excluding time for haulage and return trip complete as per specification item No 17.1 page 130 and KSRB M.100.4.1 cost of haulage excluding loading and unloading MORTH to a distance of 4.00 K.M (Item No 17.1Page 136 (SR 2018-19)	cum	98.5	Rupees Ninety Eight and Fifty Paise Only


Signature of the Contractor


Executive Engineer 21/09
Byarayanapura Division
BBMP, Bangalore - 92


21/09